



STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 2 TO PROJECT NO. 42707**

**CONSTRUCTION WORK  
REPOINT MASONRY  
BUILDINGS 10 & 11  
EASTERN CORRECTIONAL FACILITY  
INSTITUTIONAL ROAD  
NAPANOCH, NY 12458**

September 19, 2013

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.  
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**DRAWINGS**

1. Drawing A-001 Masonry Repair Keyed Note #6 to be replaced with:

3'-6" x 7'-0" SCREEN TO BE OPENED BY KEY. PRIME (TYPE ESP) AND PAINT (TYPE EAL-3). RELOCK.

2. Drawing A-001 & Drawing A-002 General Repair Keyed Note #6:

TRIM INCLUDES THE EAVE FASCIA.

3. Drawing A-001 and Drawing A-002

A. ALL WINDOWS ON BUILDING #10, FIRST, SECOND AND THIRD FLOORS HAVE ALUMINUM SCREENS TO BE REMOVED PRIOR TO PAINTING. THEY WILL REQUIRE REMOVAL OF THE SYSTEMS JAMB RETAINING TRACKS WHICH ARE ATTACHED TO THE WOOD SASH WITH SCREWS AT ROUGHLY 2'-0" ON CENTER. THEY ARE ACCESSIBLE FROM THE EXTERIOR. REINSTALL TRACK AND SCREENS AFTER PAINTING. SEE GENERAL REPAIR NOTE #1.

B. WOOD FRAME SCREENS INSTALLED OVER BARS ARE TO BE REMOVED PRIOR TO PAINTING AND REINSTALLED WHEN PAINTING IS COMPLETED. DO NOT PAINT THE WOOD FRAME SCREENS. THERE ARE APPROXIMATELY 9 INDIVIDUAL OPENINGS, EACH ROUGHLY 3'-0" X 6' - 11".

**ADDENDUM NO. #2 TO PROJECT NO. #42707-C**

- C. VARYING APPLICATIONS OF EXPANDED METAL, CHICKEN WIRE AND BUG SCREEN ARE SCREWED ONTO THE WOOD SASH AT THE BASEMENT WINDOWS AND MUST BE REMOVED PRIOR TO PAINTING. REPLACE IN KIND WHEN PAINTING IS COMPLETED.
- D. THERE ARE MISCELLANEOUS SASH CONFIGURATIONS THAT INCLUDE FANS AND LOUVERS SET IN PLYWOOD AND/OR METAL IN WINDOWS ON BUILDING #10 FOR AN ADDITIONAL 1,000 SF. SEAL/PRIME AND PAINT WITH APPROPRIATE SYSTEM AS PER SPECIFICATION SECTION 099101.
- E. CUT ALL IVY AT GRADE AND REMOVE ALL VINES FROM ALL FACADES TO FACILITATE THE WORK FOR AN ADDITIONAL 2,000 SQUARE FEET OF VINE REMOVAL.

4. Drawing A-001 Elevation 1/A-001

- A. WINDOWS 1-27 & 2-27 HAVE BAR ASSEMBLIES SIMILAR TO THE ADJACENT OPENINGS.
- B. ELIMINATE BASEMENT WINDOW B-26 FROM THE WORK SCOPE. THIS OPENING HAS BEEN BRICKED UP.
- C. THERE IS ONE ADDITIONAL 5'-0" X 7'-0" DOOR & BAR GATE AT THE BASE OF THE BASEMENT STAIRS THAT IS NOT DEPICTED ON THE ELEVATION. LABEL THIS DOOR AND GATE ASSEMBLY B-26B AND ADD IT TO THE WORK SCOPE.
- D. THERE IS ONE ADDITIONAL WINDOW SIMILAR TO WINDOW B- 30 BELOW THE FRONT DOOR RAMP AND LANDING. LABEL THIS WINDOW B-29 AND ADD IT TO THE WORK SCOPE.

5. Drawing A-001 Elevation 2/A-001

- A. WINDOWS 1-38 & 2-38 HAVE BAR ASSEMBLIES SIMILAR TO THE ADJACENT OPENINGS.
- B. THE UPPER LEFT SECOND FLOOR OPENING IS A WOOD WINDOW & BAR ASSEMBLY SIMILAR TO WINDOW 2-8. LABEL THIS WINDOW 2-16 AND ADD IT TO THE WORK SCOPE.
- C. THE EAST ELEVATION OF THE EAST CENTER WING HAS LIMITED ACCESS FOR LARGE EQUIPMENT DUE TO ADJACENT STRUCTURES. PLEASE REFER TO SITE PLAN DRAWING C-001.

6. Drawing A-001 Elevation 3/A-001

- A. WINDOWS 1-21 & 2-21 HAVE BAR ASSEMBLIES SIMILAR TO THE ADJACENT OPENINGS.

**ADDENDUM NO. #2 TO PROJECT NO. #42707-C**

B. WINDOW B-12 AND THE LOWER SASH AND BAR ASSEMBLIES OF WINDOW 1-31 ARE OBSCURED BY THE ADJACENT SHED STRUCTURE. PLEASE REFER TO SITE PLAN DRAWING C-001. PAINT WHERE ACCESSIBLE.

7. Drawing A-004 and Drawing A-005

OPERABLE IN-SWING HOPPER TYPE SASH MUST BE PAINTED FROM THE INTERIOR OF THE BUILDING.

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design