



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 42994

**ELECTRICAL WORK
REPLACE FIRE ALARM SYSTEM
PARKER TRAINING ACCADEMY
RD#3, BOX 130, ROUTE 56
TURKEY HILL ROAD
RED HOOK, NY 12571**

March 15, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. PAGE 011000-1, Paragraph 1.03-A: Delete this Paragraph in its entirety.
2. PAGE 028304-1, Paragraph 1.01-A: Delete the last sentence "The results of the testing for lead-containing materials are listed in Document 003126."

DRAWINGS

3. Drawing No. E-401:
 - a. ADD GENERAL NOTE 11 TO READ: "All underground duct bank indicated on this drawing shall consist of two (2) 4" conduits. Install three 1-1/4" innerducts in one (1) conduit only, the second conduit is a spare and shall remain empty. Provide two cables of Type LAN-O (6 optical fibers per cable in separate innerducts, arranged in a ring between the Garry, Alstork, Administration and Weis buildings. Provide only one (1) 6 strand MM fiber cable in innerduct between the Garry and Red Hook building."
4. Drawing No. E-501:
 - a. Detail 2: Change the 3"(typ) separation distance between conduits to 6"(typ) between conduits.
 - b. Detail 4: Change note to read: "The minimum distance between direct buried rigid ferrous metal conduits shall be 12."

END OF ADDENDUM

James Dirolf, P.E.
Director of Design