



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 6 TO PROJECT NO. 42998

**CONSTRUCTION WORK, HVAC WORK, PLUMBING WORK, ELECTRIC WORK
REHABILITATE KITCHEN
AND DINING AREAS
GOSHEN RESIDENTIAL CENTER
97 CROSS ROAD
GOSHEN, NY 10924**

January 13, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

C, P & E CONTRACT:

SPECIFICATIONS

NO ADDENDUM AT THIS TIME

DRAWINGS

NO ADDENDUM AT THIS TIME

H CONTRACT:

SPECIFICATIONS

1. Section 233113.
ADD paragraph 3.08 GREASE DUCT TEST
 - A. Per section M506.3.2.5 of the Mechanical Code of New York State, test the grease duct as follows:
 - B. Prior to the use or concealment of any portion of a grease duct system, a leakage test shall be performed in the presence of the code enforcement official. Ducts shall be considered to be concealed where installed in shafts or covered by coatings or wraps that prevent the ductwork from being visually inspected on all sides. The permit holder shall be responsible to provide the necessary equipment and perform the grease duct leakage test. A light test or an approved equivalent test method shall be performed to determine that all welded and brazed joints are liquid tight. A light test shall be performed by passing a lamp having a power rating of not less than 100 watts through the entire section of duct work to be tested. The lamp shall be open so as to emit light equally in all directions perpendicular to the duct walls.

- C. A test shall be performed for the entire duct system, including the hood-to-duct connection. The ductwork shall be permitted to be tested in sections, provided that every joint is tested.

DRAWINGS

NO ADDENDUM AT THIS TIME

END OF ADDENDUM