



ADDENDUM NO. 1 TO PROJECT NO. 43356

**CONSTRUCTION WORK
UTICA STATE OFFICE BUILDING
REPLACE WINDOW WALL SYSTEM, 2ND FLOOR
UTICA, NEW YORK**

January 9, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 011000-2, Paragraph 1.08 k.: Delete this Paragraph in its entirety and replace with the following:
“K. Equipment, furniture, partitions, and related items to be moved and reset by State personnel. Contractor to coordinate moves in advance with the Director’s Representative.”

2. Page 084313-3, Paragraph 1.07 A.: Delete this Paragraph in its entirety and replace with the following:
“A. Field testing of installed aluminum framed storefronts shall be performed in accordance with AAMA 503–08. Each test shall be a minimum of 6' wide and 10' tall and inclusive of the head, (2) jambs and sill. There shall be (4) tests, one on each of the four elevations. Specific locations for the (4) tests will be selected by the Director’s Representative after the windows are installed but before any interior finish work is begun. The cost of the (4) initial tests shall be included in the contractor's bid. The correction of any deficiencies observed as a result of the test and retesting due to initial test failures as determined by the Director’s Representative will be at the expense of the Contractor.”

3. Page 084313-4, Paragraph 2.03 D.: Delete this Paragraph in its entirety and replace with the following:
“D. Finish shall match existing exterior. Finish will be selected from the manufacturer’s full range of finishes and be inclusive of black. Anodic and paint finishes shall be considered.
 1. Anodic:
 - a. Finish all exposed areas of aluminum storefront and components with electrolytically deposited color in accordance with Aluminum Association Designation.
 2. Organic: 70% Kynar 500 two coat system
 - a. Finish all exposed areas of aluminum storefront and components.”

4. Page 088100-4, Subparagraph 2.01 A.1.a.: Delete this Subparagraph in its entirety and replace with the following:
 - “a. Outdoor Light: Light reflective tint as selected by the Director’s Representative, tempered, 1/4 inch thick.”

DRAWINGS

5. Drawing No. A-104, FAÇADE REPAIR LEGEND: Change “330 LF” area allowance for Scope of Work Item F-1 to read “810 LF”.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design