



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 43599

**CONSTRUCTION WORK
PROVIDE MODIFIED BITUMEN ROOF SYSTEM
50 WOLF ROAD
ALBANY, NY**

May 17, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

Page 011000-2, ARTICLE 1.05 RESTRICTED WORK PERIOD: Add the following Paragraph:

1. "B. Do not perform the roofing and related Work between December 1st and April 1st unless approved otherwise, in writing, by the Director. During this period, clear the roof of materials, equipment, and debris. Maintain the roof in a watertight condition.
 1. The above period will not be included in the number of days specified for completion of the Work."

DRAWINGS

2. Drawing H-101, ASBESTOS NOTE, Note 2: Delete this Note in its entirety and replace with the following:
 - "2. Asbestos abatement work within 25 feet of HVAC air intake locations on Main and Lower Roofs shall be performed when HVAC systems are shut down. The shut down times are as follows: Monday through Friday between 6:00 pm and 3:30 am, and all day Saturdays and Sundays. Asbestos abatement work outside the 25 foot work area shall take place during normal daytime work hours following the requirements of Code Rule 56. On the lower roof, follow the same procedure as above within 25 feet of entry locations – entry doors must remain in use during normal working hours. Coordinate removals with the Director's Representative."

3. Drawing C-101, GENERAL NOTES: Add the following Notes:
- “G. At Contractor Access Area: Remove and safely store existing 15 foot high light pole and three (3) Visitor Parking signs in contractor staging area. Remove three (3) ornamental trees. Reinstall light pole and Visitor Parking signs in original locations after the removal of the stairway access is removed. Provide three (3) ornamental trees of similar kind in original locations.”

 - H. Existing stone ballast weight is approximately 14 pounds per square foot. If this material is removed by vacuuming, the vacuum operation shall take place during nights and weekends only.”

END OF ADDENDUM

James Dirolf, P.E.
Director of Design

JWM:jc