



ADDENDUM NO. 1 TO PROJECT NO. 43602

**ELEVATOR AND ELECTRICAL WORK
REPLACE ESCALATORS
NEW YORK STATE CAPITOL
STATE STREET
ALBANY, NEW YORK**

October 16, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

SPECIFICATION GROUP (U & E CONTRACTS)

1. Page 015000-3, Change Subparagraph 1.07 B. 1 to Read:
 - “1. Temporary Partitions: Provide 8'-0" high, fire resistive temporary partitions as indicated on drawings. Partitions to be constructed from fire resistive 2 x 4 wood framing and 1/2 inch thick plywood board on exterior (public) side of partition. Secure the partitions in place without damaging existing construction. Prepare and paint partition on exterior side (public), color as coordinated with Director's Representative. Provide 1-3/4 inch thick solid core flush wood doors or 18 gage flush steel doors, and steel door frames. Equip doors with full mortise hinges and storeroom function lockset. Furnish the Director's Representative with 2 keys for each lock.
 - a. To the greatest extent possible, temporary partitions shall be constructed offsite in prefabricated panel sections to minimize field labor and disruption to the facility. Panel sections shall be erected onsite within the work hours prescribed under 011000, 1.10 Contractor Use of Premises, with the remaining fabrication taking place in a location as coordinated with the director's representative.”

ELEVATOR WORK SPECIFICATIONS (U-CONTRACT)

2. Page 143100-9, Paragraph 1.11 D: Delete this Paragraph in its entirety.
3. Page 143100-10, Article 1.12: Add the following Paragraph:
 - “C. Contractor shall remove brass and glass guardrail system as necessary to facilitate escalator equipment installations. Guardrail system shall be re-installed to the satisfaction of the Director's Representative prior to the completion of the work.
 - a. Contractor shall submit documentation reviewing removal and re-installation process of existing guardrail system to Architect, prior to initiating any work.”

DRAWINGS

ELECTRICAL WORK DRAWINGS (E-CONTRACT)

4. Drawing No. E-101, ELECTRICAL DEMOLITION AND CONSTRUCTION PLAN
CONCOURSE LEVEL: Add the following note:
 - “4. The Contractor shall maintain existing fire alarm system sequence of operation associated with escalator. All fire alarm devices including area smoke detectors, power shut down relays, control wiring etc. shall remain unless otherwise noted.”

END OF ADDENDUM

James Dirolf, P.E.
Director of Design