



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 43747

**CONSTRUCTION WORK
REPLACE ROOF
DOT REGION 5, CHAUTAUQUA COUNTY
154 CHAUTAUQUA ROAD
FREDONIA, NY 14063**

May 22, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS:

1. Appendix: Add the attached test result information to this part: Asbestos, Lead-Based Paint and PCB Inspection Report.
 - a. Letter from The Browne Company dated May 16, 2013 with composition of 2 cores indicated.
 - b. Test results from AmeriSci dated May 15, 2013 with 2 negative test results for asbestos content.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design



Please Reply To:

AmeriSci Richmond

13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-1800

FACSIMILE TELECOPY TRANSMISSION

To: Robert Barr
56 Services, Inc
Fax #:
Email: rob@56services.com,rbarr27@yahoo.com

From: C. David Mintz
AmeriSci Job #: 113051609
Subject: ELAP-PLM/TEM 24 hour Results
Client Project: 13-05029; 154

Date: Wednesday, May 15, 2013
Time: 15:30:28
Comments:

Number of Pages:

3 + cover
(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Preliminary data reported here will be verified before final report is issued. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

Certified Analysis Service 24 Hours A Day • 7 Days A Week Competitive Prices
visit our web site - www.amerisci.com

Boston • Los Angeles • New York • Richmond



AmeriSci Richmond

13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-1800

PLM Bulk Asbestos Report


56 Services, Inc
Attn: Robert Barr
PO Box 561

Buffalo, NY 14213

Date Received 05/15/13 **AmeriSci Job #** 113051609
Date Examined 05/15/13 **P.O. #**
ELAP # 10984 **Page** 1 of 1
RE: 13-05029; 154

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
01 Location: Top Roof	113051609-01	No	NAD (by NYS ELAP 198.1) by C. David Mintz on 05/15/13
Analyst Description: Brown, Homogeneous, Fibrous, Bulk Material			
Asbestos Types:			
Other Material: Cellulose 95 %, Non-fibrous 5 %			
Comment: Black coloring appears to be ink, not mastic or tar.			
02 Location: Bottom Roof (Paper)	113051609-02	No	NAD (by NYS ELAP 198.1) by C. David Mintz on 05/15/13
Analyst Description: Brown, Homogeneous, Fibrous, Bulk Material			
Asbestos Types:			
Other Material: Cellulose 95 %, Non-fibrous 5 %			
Comment: Black coloring appears to be ink, not mastic or tar.			

Reporting Notes:

Analyzed by: C. David Mintz  Date 5/15/13

*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis; NA = not analyzed; NAVPS = not analyzed / positive stop; PLM Bulk Asbestos Analysis by EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples)(NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

Reviewed By: _____

Subject: Re: Missing TAT
From: Robert Barr <rob@56services.com>
Date: 5/15/2013 11:46 AM
To: Tiffany Goodwyn <tgoodwyn@amerisci.com>

113-05-1609

24 Hr for TAT for the above, please.

Thank you,

Rob

Robert Barr
56 Services, Inc.
PO Box 561
Buffalo, NY 14213
716.341.8601
716.408.9567 (fax)
Rob@56services.com

↙

On May 15, 2013, at 11:31 AM, Tiffany Goodwyn <tgoodwyn@amerisci.com> wrote:

Good morning,

we are missing a TAT for a group of samples received today. 13-05029 2 samples collected on the 14th.

let us know when you can.

tiffany

--

Thanks For Choosing Amerisci

Tiffany Goodwyn
tgoodwyn@amerisci.com
Office: (804) 763-1200
Fax: (804) 763-1800
Toll Free: (800) 476-5227
www.amerisci.com

THE BROWNE COMPANY
Roofing and Waterproofing Consultants, Inc.
98 Forest Drive
Orchard Park, New York 14127
Phone/Fax (716) 667-0802
email: browneco@verizon.net

May 16, 2013

John Zietkiewicz, AIA, LEED, GA
Razak Associates
2060 Fairport Nine Mile Point Road, Suite 300
Penfield, NY 14526-1749

Reference: Replace Roof, DOT Region 5 – Chatauqua County
43747-C, DOT Fredonia - Core Cuts of Existing Roof

Dear Mr. Zietkiewicz

This past Tuesday morning (May 14, 2013), along with Tom Kozaczka from 56 Services, Inc., I took two core samples of the existing roof at the Fredonia DOT garage (please see Picture Nos. 1 and 2.) One sample was taken from the high roof and one sample was taken from the low roof. The results of both core cuts were identical:

- Fully adhered .060 EPDM membrane.
- 2” isocyanurate insulation.
- Reinforced kraft paper vapor barrier.
- Metal roof deck.

The reinforced kraft paper vapor barrier was tested for asbestos contamination and it came up negative.

Please do not hesitate to contact me if you have any questions or concerns regarding this proposal.

Sincerely

THE BROWNE COMPANY

Gary Browne

Gary Browne, RCI, CSI, CDT
Roof Consultant



Picture No. 1 – Sample test cut of the lower roof level.



Picture No. 2 – Sample test cut of the upper roof level.