



STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 2 TO PROJECT NO. 44080**

**CONSTRUCTION WORK  
PROVIDE ROOFING AND SIDING  
TRAINING, MAINTENANCE AND GARAGE BUILDINGS  
MacCORMICK SECURE CENTER  
300 SOUTH ROAD  
BROOKTONDALE, NY**

January 24, 2012

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**SPECIFICATIONS**

1. SECTION 033001 CAST-IN-PLACE CONCRETE (SHORT VERSION): Discard the Section bound in the Project Manual.
2. Page 087100 – 1, Subparagraph 1.01 A: Change “Steel Doors and Frames – Section 08112” to “Fiberglass Doors and Frames – Section 082200”.
3. Page 087100 – 7, Subparagraph 2.04 A: Delete “(Where existing frame is used, match hinges to size, weight and location)”.
4. Page 087100 – 7, Add the Following Article to PART 2 PRODUCTS:

**“2.05 KEYING**

- A. Continue Facility’s existing key system.
  1. Obtain keying information from the Facility through the Director’s Representative.
  2. Furnish combined cylinders with cores, springs, drivers, pins and caps, compatible with existing keying system.
  3. When lockset and cylinder are by different manufacturers, identify and furnish correct cylinder cam to operate lockset.
  4. Provide compression rings and spacers to achieve proper spacing relationship between cylinder and face of door.”

**ADDENDUM NO. 2 TO PROJECT NO. 44080-C**

**DRAWINGS**

4. NO ADDENDUM AT THIS TIME.

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design