




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 2 TO PROJECT NO. 44098

**HVAC WORK
PROVIDE DUST COLLECTION SYSTEM
MAINTENANCE BUILDING NO. 10
CAPE VINCENT CORRECTIONAL FACILITY
STATE ROUTE 12E
CAPE VINCENT, NY**

March 23, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS:

Specification Section 233113, METAL DUCTWORK, Article 1.03 SUBMITTALS, Para. C, add the following paragraph:

- “2. Furnish and turn over one copy each the latest edition SMACNA manuals as listed below to the Director’s Representative; submit directly to the OGS field address obtained at the Initial Job Meeting.
- a. HVAC Duct Construction Standards.
 - b. Round Industrial Duct Construction Standard.
 - c. Air Duct Leak Testing Manual”

DRAWINGS

Drawing No. M-501:

- a. SCHEMATIC: Delete duct smoke detector and conduit on collector between detector and junction box and arrowed notes for these items.
- b. ELEVATION 1/M-501:
 - 1) Delete smoke detector and arrowed note for this item.
 - 2) Change lowest arrowed note on left side from, “Fenwal Uniflap Valve” to, “Ground collector using MFR provided or approved grounding assembly.”
 - 3) Under arrowed note, DUST COLLECTOR: Change 5100CFM to 5000CFM.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design