



---

---

**ADDENDUM NO. 2 TO PROJECT NO. 44187**

**CONSTRUCTION WORK, HVAC WORK AND ELECTRICAL WORK  
PROVIDE VENTILATION, MAIN SCHOOL BUILDING  
VARIOUS DOCCS FACILITIES**

March 21, 2013

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**ALL CONTRACTS**

1. Note that section 001114 is an advertisement for bids for various facilities. The project is all inclusive and involves work at (4) facilities. The facilities are Livingston Correctional Facility, Lakeview Correctional Facility, Orleans Correctional Facility and Wyoming Correctional Facility. See contract documents for scope of work.

**CONSTRUCTION SPECIFICATIONS**

2. Page 074113-10, Subparagraph 2.01 B. 5. a: Change "3" to "1 ½"

**CONSTRUCTION WORK DRAWINGS**

3. Drawing No's A-101, A-102, A-103, A-503, A-601, S-201, S-202, S-203, Change all References to Underslab and Foundation Wall Insulation to Read: "2 INCHES THICK".
4. Drawing No's A-601, Detail No. 9, Change: 18" x 18" to 24" x 24".

**HVAC WORK DRAWINGS**

5. Revised Drawings:
  - a. Drawings No. M-101, M-102, M-103 and M-104; Change note 5 to read as follows; "All horizontal ductwork to be 12" above attic floor to clear CUH and lighting. Existing attic electrical conduits requiring relocation to be relocated by Electrical Contractor. Coordinate conduit removals with Electrical Contractor".
6. Addendum Drawing SK-1H: For Lakeview and Livingston Correctional Facilities, the existing DDC panel had the capability to tie into the existing facility wide control system network. A fiber optic panel is not required.

No work this addendum

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design