



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 44276

**CONSTRUCTION WORK
REPLACE ROOF, NORTH COMPOUND
VOCATION BUILDING NOS. 108 & 110
OTISVILLE CORRECTIONAL FACILITY
57 SANITORIUM AVENUE
OTISVILLE, NY**

July 9, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

BIDDING REQUIREMENTS

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last day for receipt of bids is changed from Wednesday, July 10, 2013, to Wednesday, July 17, 2013.

SPECIFICATIONS

NO ADDENDUM AT THIS TIME

DRAWINGS

2. Drawing No. A-101
 - a. ADD the following:
"NOTE: INCLUDE ABATEMENT OF DRAIN INSULATION BENEATH ROOF DECK AT ONE (1) ROOF DRAIN."
3. Drawing No. A-102
 - a. ADD the following:
"NOTE: INCLUDE ABATEMENT OF DRAIN INSULATION BENEATH ROOF DECK AT SEVEN (7) ROOF DRAINS."
4. Drawing No. A-103
 - a. ADD the following:
"NOTE:
 1. REPLACE EXISTING INTERNAL ROOF DRAINS WITH NEW DRAINS AND PIPING.
 2. REPLACE PIPING TO LAST CONNECTION ABOVE FLOOR. INSULATE NEW PIPE AND DRAIN BOWL.

3. ROOF DRAINS TO BE CAST IRON, LARGE DIAMETER SUMP, EQUAL TO SMITH 1010, JOSAM 21500, ZURN Z-100 OR EQUAL. PROVIDE WITH CAST IRON BASKETS AND UNDERDECK CLAMPS. INTERNAL LEADERS SHALL BE CAST IRON WITH EITHER NO-HUB OR LEAD AND OAKUM CONNECTIONS.
 4. INSULATE DRAIN AND LEADERS WITH 1" FIBERGLASS, FACED INSULATION."
5. Drawing No. A-104
- a. ADD the following:
"NOTE:
 1. REPLACE EXISTING INTERNAL ROOF DRAINS WITH NEW DRAINS AND PIPING.
 2. REPLACE PIPING TO LAST CONNECTION ABOVE FLOOR.
 3. ROOF DRAINS TO BE CAST IRON, LARGE DIAMETER SUMP, EQUAL TO SMITH 1010, JOSAM 21500, ZURN Z-100 OR EQUAL. PROVIDE WITH CAST IRON BASKETS AND UNDERDECK CLAMPS. INTERNAL LEADERS SHALL BE CAST IRON WITH EITHER NO-HUB OR LEAD AND OAKUM CONNECTIONS.
 4. INSULATE DRAIN AND LEADERS WITH 1" FIBERGLASS, FACED INSULATION."
6. Drawing No. A-501
- a. ADD the following to 2/A-501 and 3/A501:
"NOTE: INSULATE ANY VOIDS WHICH MAY BE UNCOVERED DURING THE DEMOLITION OF FASCIA TRIM.
 - b. REVISE 3/A-501 as follows:
 1. ADD gutter similar to that in Detail 8/A501.
 2. Provide tapered wood blocking to provide plumb gutter.
 - a. REVISE 6/A-501 as follows:
 1. REMOVE the word "EXISTING" from "DRAIN BOWL".
 2. ADD the following:
"NOTE:
 1. REPLACE EXISTING INTERNAL ROOF DRAINS WITH NEW DRAINS AND PIPING.
 2. REPLACE PIPING TO LAST CONNECTION ABOVE FLOOR.
 3. ROOF DRAINS TO BE CAST IRON, LARGE DIAMETER SUMP, EQUAL TO SMITH 1010, JOSAM 21500, ZURN Z-100 OR EQUAL. PROVIDE WITH CAST IRON BASKETS AND UNDERDECK CLAMPS. INTERNAL LEADERS SHALL BE CAST IRON WITH EITHER NO-HUB OR LEAD AND OAKUM CONNECTIONS.
 4. INSULATE DRAIN AND LEADERS WITH 1" FIBERGLASS, FACED INSULATION."

END OF ADDENDUM

James Dirolf, P.E.
Director of Design