



---

---

**ADDENDUM NO. 4 TO PROJECT NO. 44303**

**HVAC WORK AND ELECTRICAL WORK  
REPLACE ABOVE GROUND HOT WATER PIPING  
MARCY CORRECTIONAL FACILITY**

March 8, 2013

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**HVAC WORK SPECIFICATIONS**

1. Article 230923, 3.05 A. 8. a: Replace “Occupied Mode” with “Occupied (Day) Mode”.
2. Article 230923, 3.05 A. 8. b.: Replace “Unoccupied Mode” with “Unoccupied (Night) Mode”.
3. Article 230923, 3.05 A. 10.: Add paragraph below:
  - e. Day/Night Operation: VAV boxes shall reduce to minimum setting of 30% air flow (adjustable) during unoccupied (night) periods. VAV boxes shall maintain temperature per above sequences during occupied (day) periods.
4. Article 317800, 2.01 A. 1.: Replace “16 inches” with 18 inches”.

**HVAC WORK DRAWINGS**

1. Drawing M-709: Replace keyed note label “2” with keyed note label “4” at the following points in the Points List: ZONE 1 SPACE TEMPERATURE, ZONE 2 SPACE TEMPERATURE, ZONE 3 SPACE TEMPERATURE, and ZONE 4 SPACE TEMPERATURE. These sensors shall be replaced.
2. Drawing M-711: Add the following General Note:
  1. Fan EF-4 is located in the accessible chase space immediately to the north east of the room in which the DDC panel is located. Fan EF-5 is located in the accessible chase space immediately northwest of the room labeled “Secretary”.
3. Drawing M-712: Delete control points referencing P-1A and P-2A (4 total). These pumps do not exist.

**ELECTRICAL WORK CONTRACT**

No work this addendum

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design