



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 44312

**CONSTRUCTION WORK
REPAIR MASONRY
BUILDING NO's. 8, 9, 11, 13, 14, 15, 18, 33 & 61
MOUNT MCGREGOR CORRECTIONAL FACILITY
1000 MOUNT MCGREGOR ROAD
WILTON, NEW YORK 12831**

April 10, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

REFER TO DRAWINGS

1. In addition to the quantity and graphic illustration of “stucco repairs” shown on the bidding documents, add an additional 1,000 square feet (total) of stucco repairs to the project. This additional quantity is distributed amongst all of the buildings of the project. This work item is denoted on the bid drawing legend as “Areas of stucco cracks or missing stucco”.
2. In addition to the quantity and graphic illustration of “Clean stone masonry, Remove Lime” shown on elevation #1 on bid drawing B13/61-101-C , add an additional 500 square feet (total) of stone cleaning to the project. This additional cleaning will be done in the same general area of Building 13/61.

DIVISION 09 – FINISHES

1. Delete the following from specification section 099101 CONSTRUCTION PAINTING, 1.02, C
“Existing Exterior Paint Film Stripping and Removal Submittals”
 - a. Depending upon the substrate to be stripped and thickness of paint films to be removed, acceptable methods of removal include hand or mechanical tools, pressure washing with water, heat or steam devices, chemical strippers and other appropriate methods.

And replace with:

- a. Depending upon the substrate to be stripped and thickness of paint films to be removed, acceptable methods of removal include hand or mechanical tools, pressure washing with water, chemical strippers and other appropriate methods.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design