



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 2 TO PROJECT NO. 44361

**CONSTRUCTION WORK
REPLACE ROOF,
MAINTENANCE HEADQUARTERS
DOT REGION 8, ROCKLAND COUNTY
275 RIDGE ROAD, NEW CITY, NY 10956**

April 16, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

DRAWINGS:

3. Drawing A-503, NOTES: Add No. 7 - Provide Hot Water Heater Chimney Pipe of the same material as boiler chimney material as specified and sized to match existing. For estimating proposes use 4" dia. x +/-40' long double wall stainless steel pipe. Run hot water heater chimney pipe up through the existing clay tile chimney flue adjacent to the new stainless steel boiler pipe, provide required hangers and clamps to secure hot water chimney pipe the full length.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design