



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO.1 TO PROJECT NO. 44415-C

CONSTRUCTION WORK
Provide Adhered EPDM Roof System
Bridge Crew Facility
DOT Region 4, Monroe County
3837 Monroe Avenue
Pittsford, NY 14534

February 05, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

1. The contract document A-101 states, GENERAL NOTES: 1. AT ROOFS "A", "C", "E" AND "F" REMOVE AND DISPOSE OF THE EXISTING HYPALON ROOF SYSTEM DOWN TO THE EXISTING FILL MATERIAL/CONCRETE ROOF DECKS. SYSTEM INCLUDES BUT NOT LIMITED TO: ADHERED 3" RIGID INSULATION AND TAPERED INSULATION CRICKETS, VAPOR BARRIER, METAL GRAVEL STOPS, METAL COPING AND FLASHINGS. AT ROOFS "B" AND "D" REMOVE AND DISPOSE OF THE EXISTING SHINGLED ROOF SYSTEM DOWN TO THE EXISTING WOOD DECK. REFER TO DRAWINGS A-101 THRU A-104 FOR PLANS AND DETAILS.
2. Change to READ: GENERAL NOTES: 1. AT ROOFS "A", "C", "D" AND "F" REMOVE AND DISPOSE OF THE EXISTING HYPALON ROOF SYSTEM DOWN TO THE EXISTING FILL MATERIAL/CONCRETE ROOF DECKS. SYSTEM INCLUDES BUT NOT LIMITED TO: ADHERED 3" RIGID INSULATION AND TAPERED INSULATION CRICKETS, VAPOR BARRIER, METAL GRAVEL STOPS, METAL COPING AND FLASHINGS. AT ROOFS "B" AND "E" REMOVE AND DISPOSE OF THE EXISTING SHINGLED ROOF SYSTEM DOWN TO THE EXISTING WOOD DECK. REFER TO DRAWINGS A-101 THRU A-104 FOR PLANS AND DETAILS.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design