



STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 1 TO PROJECT NO. 44425**

**CONSTRUCTION WORK  
REPLACE ROOF, AND REPOINT BUILDING 22  
NEW YORK STATE OFFICE OF MENTAL HEALTH  
BUFFALO PSYCHIATRIC CENTER  
400 FOREST AVENUE  
BUFFALO, NY 14213**

June 7, 2013

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.  
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**SPECIFICATIONS**

1. 076000 FLASHING AND TRIM – Part 2, Para 2.04, C.  
Add new subparagraph:  
“6. Aluminum: Minimum 0.050inch.”

**DRAWINGS**

1. Drawing No. A100: KEYNOTES
  - a. Revise Keynote 1 to read:  
“Remove existing ballasted roofing system in its entirety, down to the existing structural deck. Existing system to include Stone Ballast, EPDM Membrane, 2” Tapered and/or Rigid Insulation, Felt Paper and Mopping Tar Vapor Barrier. Refer to Detail 2/A100 for structural deck material.”
  - b. Revise Keynote 23 to read:  
“Remove existing ballasted roofing system in its entirety, down to the existing structural deck. Existing system to include Stone Ballast, EPDM Membrane, 2” Tapered and/or Rigid Insulation, ½” Gypsum Board, Felt Paper and Mopping Tar Vapor Barrier. Refer to Detail 2/A100 for structural deck material.”
2. Drawing No. A100, Detail 2/A100:
  - a. Revise Title of Detail to Read:  
“Existing Structural Deck Material”

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design