




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 44490

**CONSTRUCTION WORK, PLUMBING WORK
REPLACE ROOF, BUILDING 6
ELMIRA CORECTIONAL FACILITY
1879 DAVIS STREET
ELMIRA, NEW YORK 14902**

March 04, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 076000-3, Article 2.04: Delete Paragraph F in its entirety.
2. Page 075323-9, Change Paragraph 2.02 F. to Read:

“Tapered Cricket System: Membrane manufacturer’s approved 1/2 inch per foot factory tapered isocyanurate insulation conforming to ASTM C 1289.”

CONSTRUCTION WORK DRAWINGS

3. Drawing A-101:
 - a. DETAIL 1-ROOF PLAN: Change All Tapered Cricket System Slopes to $\frac{1}{2}$ ” *Per Foot*.
4. Drawing A-101:
 - a. DETAIL 1-ROOF PLAN: The two (2) roof drains being provided at the north end of the building to be located 22’-0” +/- from the north end of the building, and the two (2) roof drains being provided at the south end of the building to be located 22’-0” +/- from the south end of the building. Contractor shall verify all conditions from the underside of the roof deck with the Director’s Representative prior to drilling roof penetrations.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design