



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 44495

PLUMBING WORK

**PROVIDE PROGRAMMABLE FLUSHOMETERS, S-BLOCK, BLDG. 38
CAYUGA CORRECTIONAL FACILITY
ROUTE 38A
MORAVIA, NEW YORK 13118**

February 26, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

PLUMBING DRAWINGS

1. Drawing Nos. P-001 through P-601:

Sequence of Work shall be as follows:

- a. Perform all electrical work as indicated on the Contract Drawings prior to removing existing push buttons and flush valves found at each combination security fixture.
- b. After electrical work has been completed; removal of existing push buttons and flush valves at combination security fixtures shall commence. Contractor shall coordinate providing electronic push buttons, flush valves and final electrical connections at each cell with Director's Representative. Number of cells that can be out of service at one time shall not exceed four (4) cells. All work within the four (4) cells out of service shall be complete and operational prior to starting work on the next set of four (4) cells.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design