



STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 2 TO PROJECT NO. 44512-C**

**CONSTRUCTION WORK  
REPLACE ROOFS, BUILDINGS, 1, 12, 13-19  
CAPE VINCENT CORRECTIONAL FACILITY  
PO BOX 599, NYS ROUTE 12E  
CAPE VINCENT, NY**

November 1, 2013

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**DRAWINGS**

1. Drawing A-104:
  - a. Detail D/A-104; Typical Elevation Perpendicular: REVISE the note above the roof to read "REPLACE PREFORMED METAL SIDING SYSTEM CONCURRENT WITH ADJACENT ROOFING PANELS."
  - b. Detail E/A-104, Typical Roof Plan: REMOVE the notation "NIC" depicted in the upper region of the Roof Plan. All roof areas are subject to this contract.
  - c. NOTE 3: REVISE second sentence to read: "PROVIDE APPROX. 45 SQ FT OF POINTING & 35 BRICKS TO MATCH EXISTING TOTAL FOR ALL BUILDINGS."
2. Drawing A-501:
  - a. Detail 3/A-501, Flashing Detail: REVISE siding note to read "PROVIDE PREFORMED METAL SIDING SYSTEM".
3. Drawing A-502:
  - a. Detail 2 and 10/A-502: REPLACE the note "EXISTING SIDING" with "PROVIDE PREFORMED METAL SIDING SYSTEM" for Building 12 only.
  - b. Detail 4 and 5/A-502: REPLACE the note "REMOVE/REPLACE EXIST. SIDING TO INSTALL METAL BASE FLASHING" with "PROVIDE PREFORMED METAL SIDING SYSTEM".

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design