



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 2 TO PROJECT NO. 44547

**CONSTRUCTION WORK, HVAC WORK, PLUMBING WORK, AND ELECTRICAL WORK
REHABILITATE SHOWERS
MAIN HOUSING UNITS 2, 3, 5, 7, 8 AND 34
CLINTON CORRECTIONAL FACILITY
ROUTE 374
COOK STREET
DANNEMORA, N.Y.**

March 7, 2013

<p>NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

CHANGES TO ADDENDUM NO.1

1. Item No.4.d.: Delete Structural Steel Fabrication / Erection Note Nos. 6 and 7 in their entirety, and replace with the following:
“6. TORCH CUTTING AND FIRE WATCH DURATION AS PER DIRECTOR’S REPRESENTATIVE.”

CONSTRUCTION WORK DRAWINGS

2. Drawing No.S-100: STRUCTURAL STEEL FABRICATION / ERECTION NOTES, Note Nos. 6 and 7: Delete these Notes in their entirety, and replace with the following:
“6. TORCH CUTTING AND FIRE WATCH DURATION AS PER DIRECTOR’S REPRESENTATIVE.”
3. Drawing No.H-401, DETAIL 3: Change the Note “REMOVE PAINTED MASONRY SHOWER STALL WALLS” to read “REMOVE PAINT ON MASONRY SHOWER STALL WALLS APPROXIMATELY 7 FOOT HIGH”.
4. Drawing No.A-401, DETAIL 3: Change the Note “REMOVE SHOWER STALL WALLS” to read “REMOVE APPROXIMATELY 7 FOOT HIGH MASONRY SHOWER STALL WALLS”.

HVAC WORK DRAWINGS

5. Drawing No.M-100: GENERAL NOTES, Note No. 5: Delete this Note in its entirety, and replace with the following:
 - “5. TEST AND BALANCE THE EXISTING IN LINE EXHAUST FANS PRIOR TO REMOVALS. ALSO TEST AND BALANCE THE REPLACED INLINE EXHAUST FANS AND ALL ASSOCIATED DUCTWORK TO THE SHOWERS AFTER EACH PHASE”.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design

JRC/JT: jc