




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 2 TO PROJECT NO. 44683

**CONSTRUCTION WORK
UPGRADE CONCESSION STAND
DEPARTMENT OF LABOR
BUILDING 12
STATE OFFICE BUILDING CAMPUS
1220 WASHINGTON AVENUE
ALBANY, NEW YORK 12226**

April 7, 2014

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATION GROUP

1. Page 011000-1, Paragraph 1.02 B: Add the following subparagraphs:
 - “1. The temporary store location is an existing storage room, adjoining the current store space. (See Revised Drawing ASB-101.)
 2. The contractor shall relocate to the temporary store location eight (8) existing shelving units and one (1) freezer designated by the owner’s representative. All product shall be re-located by the owner to the new temporary store location.”

DRAWINGS

2. Drawing A-102:
 - a. Floor Plan:
 - 1) Add: Elevation Marker #9 to the west wall of Room 101.
 - 2) Change: Elevation Marker #9 to #10 in Room 100.
3. Drawing A-103:
 - a. Detail #7: Add note:

“Provide ¾” x ¾” x 1/8” aluminum angles. Color to match perforated infill panel. Secure to existing metal frame.”
 - b. General Equipment Notes: Add note:

“The existing safe is bolted to the floor and after re-location to the new location the safe shall be re-bolted to the floor. The physical dimensions of the safe are 24” x 24” x 18”.”

4. Drawing A-104:
 - a. Elevation #1: Add the following notes:

“New infill panel at former door opening:
Accurate Perforating (1-800-621-0275)
Pattern: SQ015 - .500” x .687”
Finish: Powder coat both sides. Color to be selected by architect thru the Director’s Representative from the manufacturer’s standard colors.
Provide 3/4” x 3/4” x 1/8” aluminum angles. Color to match perforated infill panel. Secure to existing metal frame.”
 - b. Elevations 4, 5 and 6: Change: “Equipment Item #57” to “Equipment Item #56”.
5. Revised Drawing:
 - a. Drawing ASB-101, noted “REVISED DRAWING, dated 02/18/14” accompanies this Addendum and supersedes the same numbered originally issued drawings.
 - 1) Asbestos Abatement Notes: Add the following note:

“22. Remove existing acoustic ceiling tiles as necessary for removal of ACM debris indicated in note 21. Removed tiles shall be packaged and labeled as noted in note 9. Replace removed ceiling tiles with acoustic tile to match existing adjacent tile.”

END OF ADDENDUM

Margaret F. Larkin
Acting Executive Director

