



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 4 TO PROJECT NO. 44710

**CONSTRUCTION WORK and HVAC WORK
REPLACE WINDOWS
INDUSTRY BUILDINGS 9, 10 & 11
PHASE 1 – SOUTH FAÇADE
ROUTE 374
COOK STREET
DANNEMORA, NY**

September 30, 2014

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Section 099101 Construction Painting; paragraph D.1.b – **CHANGE** paint type designation for security bar anchor from EAL-2 to ESP.

DRAWINGS

CONSTRUCTION WORK DRAWINGS

1. Drawing A-105:
 - A. **DELETE** Removal Note # 2.
 - B. **REVISE** Note #3 to read: “Disconnect and remove mechanical window operator in its entirety. Refer to Detail 3/A-100.”
2. Drawing A-108 - Wall replacement is required. **REVISE** Removal Note #2 to read: “Disconnect toilet partition from window system. Salvage for reinstallation.”
3. Drawing A-109: **ADD** Keyed Note #2 “Infill GWB partition (full height) due to window removal and installation work. Match existing width., Paint system IAL-2”
4. Drawing A-112:
 - A. **ADD** Designation CMU at 8’-0” high at Room B-27.
 - B. **ADD** Designation GWB at 10’-0” high at Room B-39.
5. Drawing A-114: **ADD** partial CMU wall infill (full height) between Rooms 1-7 and 1-8A., paint system IAL-2

6. Drawing A-117: **ADD** Keyed Note #3 “Infill GWB (gypsum wall board) ceiling system along south wall in Rooms 2-5, 2-11 and 2-13 due to window removals and installations in these areas. Match existing heights, paint system IAL-1”
7. Drawing A-118:
 - A. **ADD** partial GWB infill (full height) between rooms 2-5#6 and 2-5#7, 2-5#8 and 2-5#9, 2-5#10 and 2-5#11, and 2-5#12 and 2-7A due to window removals and installation work. Paint system IAL-2
 - B. Detail 1 – **ADD** GWB ceiling replacement to Room 2-7A; Paint system IAL-1.
 - C. Detail 2 - **ADD** GWB wall infill between Rooms 2-28 and 2-27, Paint system IAL-2.
8. Drawing A-120: **ADD** partial GWB wall infill (full height) between Rooms 3-14 and 3-15, 3-24A and 3-1 and Room 4-13 due to window removals and installations. Paint system IAL-2.
9. Drawing A-122: HVAC contractor is reinstalling ductwork. **DELETE** keyed note #4 and indicated keyed notes in Rooms B-27 and B-39.
10. Drawing A-201:
 - A. **DELETE** the section tag 3/A-502. Sill replacement is not required in Building 10.
 - B. **CHANGE** keyed note #3 to read “Not Used”.
11. Drawing A-202:
 - A. Cast-in-place concrete sill replacement shall be included on all first and second floor windows as shown in details 3/A-501 and 3/A-502.
 - B. **CHANGE** keyed note #3 to read “Not Used”.
12. Drawing A-204:
 - A. **CHANGE** detail tag designation 3/A502 to 1/A502 in 1/A-204.
 - B. **CHANGE** 2/A-204 – the window designation for the Building 10 Basement Room B-33A is 5A as shown on Drawing A-112.
13. Drawing A-501:
 - A. Tile is required to be removed at the total window perimeter; head, jambs and sill. This removal shall be typical to that shown on details 4, 5, 6 and 7 on Drawing A-501.
 - B. Detail 2 - **ADD** paint designation “ESP” at security anchor bars to be cut back flush with face of concrete.

END OF ADDENDUM

Margaret F. Larkin
Executive Director