




STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 4 TO PROJECT NO. 44770**

**CONSTRUCTION WORK, HVAC WORK, PLUMBING WORK, ELECTRIC WORK  
REHABILITATE BATHROOMS  
HIGHLAND RESIDENTIAL CENTER  
629 NORTH CHODIKEE LAKE ROAD  
HIGHLAND, NEW YORK 12528**

February 6, 2014

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.  
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**SPECIFICATIONS**

1. SECTION 028213 ASBESTOS ABATEMENT
  - a. Paragraph 1.01 B, Building 29:
    - 1) FLOOR TILE: Add the following subparagraph:
      - “a. Remove furniture bolted to the floor. Discard existing fasteners. Clean furniture of all residual ACM dust or debris, turn over to the Facility and store where directed.”

**CONSTRUCTION WORK DRAWING**

2. Drawing HM-003:
  - a. PCB Caulk Removal Note P-2:
    - 1) Change the last sentence to read:  
"MATERIALS CONTAINING BOTH ASBESTOS AND PCBs SHALL BE REMOVED UNDER ASBESTOS ABATEMENT CONDITIONS AND DISPOSED OF AS A PCB BULK PRODUCT WASTE."
3. Drawing A-601:
  - a. Room Finish Schedule:
    - 1) Rooms R1 through R16:
      - a) Floor Finish: Change “ECT” to “CARPET”.
      - b) Base Finish: Change “ECT” to “VINYL”

**ADDENDUM NO. 4 TO PROJECT NO. 44770**

**ELECTRICAL WORK DRAWINGS**

4. Drawings E-104 and E-105:
  - a. Electric Plan Keyed Notes:
    - 1) Keyed Note 1: Change "PANEL L2A" to "PANEL LP-1".
    - 2) Keyed Note 4: Insert the following after "PANELBOARD MDP" and before "PROVIDE CIRCUIT BREAKER":
      - a) "LOCATED IN MECHANICAL ROOM".

**END OF ADDENDUM**

James Dirolf, P.E.  
Director of Design