




STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO.2 TO PROJECT NO. 44788  
HVAC WORK AND ELECTRICAL WORK  
REPAIR AND UPGRADE FACILITY HEATING SYSTEM  
AND CONTROLS  
SHAWANGUNK CORRECTIONAL FACILITY  
750 PRISON ROAD  
WALLKILL, NY**

March 6, 2015

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**HVAC DRAWINGS**

1. Drawing M-601: FINNED –TUBE RADIATION SCHEDULE, Change: Fin tube tag FT-1, Type E – Pedestal with custom enclosure change the value in the FINS PER FOOT COLUME from 40 to 50.
2. Drawing M-601: FINNED –TUBE RADIATION SCHEDULE: Change: Remark 6 to the following: “PRIVIDE 14 GAUGE FULL HEIGHT BACK PLATE.”
3. Drawing M-117: Change Keyed Note #4 to  
“SEE DETAIL 5/M-501 FOR COIL PIPING CONNECTIONS FOR THE HOT WATER AND THE CHILLED WATER COIL CONNECTIONS.”
4. Drawing M-118: Add Keyed Note #15 to the KEYED NOTES:  
“SEE DETAIL 5/M-501 FOR COIL PIPING CONNECTIONS FOR THE HOT WATER AND THE CHILLED WATER COIL CONNECTIONS.”
5. Drawing M-118: Add Keyed Note #15 designator to FCU-1, FCU-2, FCU-3 and FCU-4.

**ELECTRICAL DRAWINGS**

6. Drawing E-102: Change Keyed Note #2 to:  
“TEMPORARILY DISCONNECT AND REMOVE ALL LIGHT FIXTURES, EXIT SIGNS, SPEAKERS, AND ASSOCIATED SUPPORT HARDWARE TO ALLOW FOR CEILING WORK. MAINTAIN LIGHTING AND SPEAKER CIRCUITS FOR RECONNECTION. STORE FIXTURES AND SPEAKERS FOR REUSE. PROVIDE TEMPORARY LIGHTING OF 20FC UNTIL FIXTURES ARE RE-INSTALLED.”

**ADDENDUM NO. 2 TO PROJECT NO. 44788-H, E**

7. Drawing E-106: Change Keyed Note #2 to:  
“RE-INSTALL LIGHT FIXTURES, EXIT SIGNS, AND SPEAKERS IN LOCATIONS INDICATED. PROVIDE 3/4" CONDUIT AND CONDUCTORS (2 #12, #12G) TO EXTEND LIGHTING CIRCUIT AS REQUIRED. PROVIDE 3/4" CONDUIT AND SPEAKER CABLE MATCHING EXISTING TO EXTEND SPEAKER CIRCUIT AS REQUIRED. PROVIDE ALL HARDWARE (HANGERS AND SUPPORTS) TO RE-INSTALL LIGHT FIXTURES AND DEVICES SHOWN.”
  
8. Drawing E-107: Change Keyed Note #1 to:  
“TEMPORARILY DISCONNECT AND REMOVE ALL LIGHT FIXTURES, FIRE ALARM DEVICES, FIRE ALARM CIRCUITING, EXIT SIGNS, SPEAKERS, AND ASSOCIATED SUPPORT HARDWARE TO ALLOW FOR CEILING WORK. MAINTAIN LIGHTING AND SPEAKER CIRCUITS FOR RECONNECTION. STORE FIXTURES AND SPEAKERS FOR REUSE. PROVIDE TEMPORARY LIGHTING OF 20FC UNTIL FIXTURES ARE RE-INSTALLED. OBTAIN SERVICES OF FACILITIES FIRE ALARM VENDOR FOR RELATED WORK.”
  
9. Drawing E-107: Change Keyed Note #2 to:  
“RE-INSTALL LIGHT FIXTURES, FIRE ALARM DEVICES, EXIT SIGNS, AND SPEAKERS IN LOCATIONS INDICATED. PROVIDE 3/4" CONDUIT AND CONDUCTORS (2 #12, #12G) TO EXTEND LIGHTING CIRCUIT AS REQUIRED. PROVIDE 3/4" CONDUIT AND SPEAKER CABLE MATCHING EXISTING TO EXTEND SPEAKER CIRCUIT AS REQUIRED. PROVIDE 3/4" CONDUIT AND FIRE ALARM CABLE MATCHING EXISTING TO EXTEND FIRE ALARM CIRCUIT AS REQUIRED. OBTAIN SERVICES OF FACILITIES FIRE ALARM VENDOR FOR RELATED WORK. PROVIDE ALL HARDWARE (HANGERS AND SUPPORTS) TO RE-INSTALL LIGHT FIXTURES AND DEVICES SHOWN.”
  
10. Drawing E-401: Change Keyed Note #2 to:  
“DISCONNECT AND REMOVE LIGHT FIXTURE, ASSOCIATED CONDUIT, CONDUCTORS, AND SUPPORT HARDWARE TO ALLOW FOR HVAC INSTALLATIONS. RETAIN CIRCUIT AND LIGHT FIXTURES FOR LIGHT FIXTURE RELOCATION AND RECONNECTION.”
  
11. Drawing E-403: Change Keyed Note #1 to:  
“CLEAN, RELAMP, AND REINSTALL LIGHT FIXTURE. PROVIDE 2#12 AND #12G CONDUCTORS IN 3/4" CONDUIT TO RECONNECT FIXTURE TO EXISTING CIRCUIT. PROVIDE ALL HARDWARE (HANGERS AND SUPPORTS) TO RE-INSTALL LIGHT FIXTURES. MAINTAIN EXISTING SWITCHING CONFIGURATION.”

**END OF ADDENDUM**

Margaret F. Larkin  
Executive Director