



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 5 TO PROJECT NO. 44803

**ELECTRICAL WORK:
REPLACE PERIMETER FENCES, PERIMETER SYSTEMS & REDIRECT DRAINAGE
SULLIVAN CORRECTIONAL FACILITY
325 RIVERSIDE DRIVE
FALLSBURG, NY 12733-0115**

October 14, 2015

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Specification Section 055000:
 - a. Page 055000-1: Paragraph 1.02, Delete reference to:
“B. Field Painting: Section 099101”.
 - b. Pages 055000-1 through 055000-7: Delete All references to Section 099101.
 - c. Page 05000-3: Article 2.01, Add the Following Paragraph:
“G. Cold Galvanizing Compound: Single component compound giving 93 percent pure zinc in the dried film, and meeting the requirements of DOD-P-21035A (NAVY).”
 - d. Page 05000-7: Article 3.02, Add the Following Paragraph:
“E. Wire brush and repair welded and abraded areas of galvanized surfaces with ne coat of cold galvanizing compound.”
2. Specification Section 265533:
 - a. Page 265533-2: Replace paragraph 2.04, A, with the following:
“A. Stainless Steel boxes, gasketed cover, size as indicated on drawings; Hoffman’s Bulletin A-4 NEMA Type 4X stainless steel enclosure (NEMA 4X). Fasten cover with vandal resistant, stainless steel screws.”
3. Specification Section 281607:
 - b. Page 281607-10: Paragraph 2.01, A: Replace Company name address and telephone number, with the following:
“ECSI International, Inc., 790 Bloomfield Ave., Building C Suite 1, Clifton, NJ 07012, Telephone: 973-574-8555.”

DRAWINGS

4. Drawing Nos. C-132, C-134, E-208, E-209, E-210 AND E-211:
 - a. Add the following notes:

NOTES - REMOVAL OF EXISTING MICROWAVE AND INFRARED ZONES;

 - A. Removal of the existing microwave zones and existing infrared zone shall be in accordance with the project phasing plan and shall not be performed until after the replacement microwave zones and infrared zones are in place, operational and successfully tested.
 - B. Removals shall include all above ground equipment (sensors, poles, junction boxes, etc.), concrete bases in their entirety. Removal of concrete bases shall include the four un-used concrete bases (where the microwave units were located previous to their current locations).
 - C. All cabling shall be removed and conduit cut back to 18 inches below grade.
5. Revised Drawing:
 - a. Drawing No. E-108, noted "E-108 (REV.1)" is attached to this Addendum and supersedes the drawing bound in the Contract Documents.
6. Drawing No. E-202:
 - a. Add the following note to the General Notes:

"G. Refer to Details on Drawing No. E-511 regarding materials and installation of conduit system on the Taut Wire Fence."
7. Drawing No. E-502:
 - a. Security Fence Lighting Fixture Installation Detail:
 1. Change reference "SEE NOTES 1 AND 2" to read "SEE NOTES 2 AND 3".
 2. Change reference "NEMA 4 (CAST BOX)" to read "NEMA 4X (Stainless Steel)."
 - b. Specific Notes (Security Fence Lighting Fixture Installation Detail):
 1. Delete Note No. 1 in its entirety.
 2. Note No. 2: Change reference "NEMA 4 (CAST BOX)" to read "NEMA 4X (Stainless Steel)."
8. Addendum Drawing:
 - a. Drawing No. E-511, titled "TAUT WIRE FENCE AND ALARM SYSTEM CONDUIT DETAILS" (noted: "10/14/2015 ADDENDUM DWG) accompany this Addendum and form part of the Contract Documents.

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction

