STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 1 TO PROJECT NO. 44871

CONSTRUCTION WORK
FUEL TANK MODIFICATION AND ENVIRONMENTAL REMEDIATION
NORTHERN REGION
VARIOUS FACILITIES

August 13, 2014

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

CONSTRUCTION WORK SPECIFICATIONS

1. Page 231323-13, Subparagraph 2.12 A.2.g.: Delete this Subparagraph in its entirety and replace with the following:
   "g. Adjustable stabilizer bar."

2. Pages 231323-14 and 231323-15, Subparagraphs 2.13 B.1., 2.13 C.1, and 2.13 D.1.: Delete these Subparagraphs in their entirety and replace with the following:
   "1. Explosion Resistant Housing: NEMA Type 8 rated enclosure for Class I, Groups B, C and D."

CONSTRUCTION WORK DRAWINGS

3. Drawing Nos. C-04, and C-07: Add pressure/expansion relief valve in supply piping between emergency valve and solenoid valve.

4. Drawing Nos. C-05, C-06, C-08, and C-09: Add pressure/expansion relief valve in supply piping between shut off valve and solenoid valve.

END OF ADDENDUM

Margaret F. Larkin
Acting Executive Director