



DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 1 TO PROJECT NO. 44935

**CONSTRUCTION WORK
REPLACE METAL AND EPDM ROOFS
CAYUGA CORRECTIONAL FACILITY
PO BOX 1150
ROUTE 38A
MORAVIA, NY 13118-1150**

September 2, 2015

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

TITLE PAGE (COVER)

1. **CORRECT THE PRE-BID SITE VISIT SCHEDULED ON SEPTEMBER 13, 2015 TO SEPTEMBER 3, 2015.**

SPECIFICATIONS GROUP

2. Remove 075323, 2.08, C in its entirety and replace with the following:
 - C. Material for Vapor Retarder – Self Adhered over Underlayment: Composite membrane 40-mil thick, consisting of a minimum 32-mils of self-adhering rubberized asphalt laminated to an 8-mil polyester fabric, or 5 mil skid resistant polyethylene film conforming to ASTM D 412, ASTM D 146 and ASTME-154.
 1. Primer: Manufacturer’s recommended primer.
 2. Tapes: As recommended by Manufacturer.
3. Add the following to 075323, 2.08
 - D. Materials for Vapor Retarder - Torched over Concrete Decks and Existing Vapor Retarders:
 1. Primer: Water-based, polymer modified, asphalt primer.

2. Smooth surfaced SBS asphalt elastomer sheet reinforced with a combination of polyester fabric/fiberglass scrim composite ASTM 6162 Type II, a fiberglass scrim ASTM D 6163 Type I, or a polyester fabric ASTM D 6164 Type I.
 - a. Grade S.

DRAWINGS

4. Drawing A-107 (Building #11), under “Provided Roof System Description”

Omit the following bullet point:

“2 Ply Vapor Retarder (Torched)”

And replace with the following:

“Vapor Retarder - Self Adhered”

5. Drawing A-111 (Building #21), under “Provided Roof System Description”

Omit the following bullet point:

“2 Ply Vapor Retarder (Torched)”

And replace with the following:

“Vapor Retarder - Self Adhered”

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction