




STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 1 TO PROJECT NO. 44956**

**CONSTRUCTION WORK, HVAC WORK, PLUMBING WORK, ELECTRIC WORK  
REPLACE SUPPLY & RETURN  
HOT AND COLD WATER PIPING  
BLDGS. 143, 144, 152  
GROVELAND CORRECTIONAL FACILITY  
7000 SONYEA ROAD, ROUTE 36  
SONYEA, NY**

June 1, 2016

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.  
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**C CONTRACT:  
DRAWINGS**

1. DRAWING SHEETS A-102, A-103, A-104, A-106, A-107, A-108, A-110, A-111, A-112
  - a. Revise Key Note No. 1 to read as follows:

“AREA OF CEILING REPLACEMENT. REMOVE EXISTING LIGHTING, SUSPENDED GYPSUM CEILING SYSTEM **INCLUDING FLATTENED EXPANDED METAL MESH.** SEE ELECTRICAL DRAWINGS FOR SCOPE OF ELECTRICAL WORK.”
2. DRAWING SHEET A-103
  - a. Delete the following two (2) notes, found on the sheet to the northeast of the floor plan, in their entirety:

“600T125-33 PERIMETER TRACK WITH (2) ¼” TAPCONS AT 32” ON CENTER AND AT BOTH ENDS INTO BLOCK WALL.”

“600S162-54 BEAM 8” BACK FROM CORNER. UTILITY CLIP UA-135-12 WITH (3) #10 SCREWS INTO CFS AND (6) ¼” TAPCONS INTO BLOCK WALL, BOTH ENDS.”
3. DRAWING SHEETS A-101 THROUGH A-124
  - a. Add the SYMBOLS LEGEND shown on attached sketch SK-1.

## ADDENDUM NO. 1 TO PROJECT NO. 44956

### P-CONTRACT: DRAWINGS

1. DRAWING SHEET P-001
  - a. Add the following notes:
    1. **Provide an Expansion Loop in all 2-1/2 inch Type “L” Copper Domestic Hot Water Piping as follows:**
      1. **Four elbow “U” shape with an overall dimension (Length or “L”) equal to 13 feet 6 inches.**
      2. **Height (H) is equal to 5 feet 5 inches.**
      3. **Width (W) is equal to 2 feet 8 inches.**
      4. **Length equals 2”H” + “W”**

**Anchor to Anchor locations shall not exceed 120 feet. Loop shall be centered between anchors. Piping between anchors shall be supported, NOT ANCHORED.**

2. **Refer to CPVC Expansion Loop Sizing Schedule 3/P-001 for clarity.**
2. DRAWING SHEET P-401
    - a. DETAIL 2 / P-401, ENLARGED PLAN – PLUMBING

Revise the following note:

“REMOVE AND REINSTALL EXISTING SERVICE SINK (BUILDING 152)”

to read as follows:

“REMOVE AND REINSTALL EXISTING SERVICE SINK (BUILDING 152, **ONLY**)”

See attached SK-2, showing Partial Sheet P-401 for clarification.

**END OF ADDENDUM**


Margaret F. Larkin  
Executive Director  
Design and Construction

# SYMBOLS LEGEND:


MATCH LINE:



DETAIL MARKER:



INTERIOR ELEVATION MARKER:



NYS OFFICE OF GENERAL SERVICES

*Serving New York*

CONTRACT:	CONSTRUCTION
PROJ. NO:	44956
DATE:	05/31/16
DRAWN:	TJR
APPROVED:	TCO



**BERNIER CARR & ASSOCIATES**  
engineers • architects • land surveyors

ADDENDUM #1 REFERENCE DRAWING:

SHEET TITLE: SYMBOLS LEGEND

PROJECT: HOT AND COLD WATER PIPING  
BLDGS. 143, 144 & 152

WARNING: THE ALTERATION OF THIS MATERIAL IN ANY WAY, UNLESS DONE UNDER THE DIRECTION OF A COMPARABLE PROFESSIONAL, I.E. ARCHITECT FOR AN ARCHITECT, ENGINEER FOR AN ENGINEER OR LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR REGULATIONS AND IS A CLASS 'A' MISDEMEANOR.

DWG NO:  
SK-1

