

**DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 2 TO PROJECT NO. 44985

**HVAC WORK AND ELECTRICAL WORK
PROVIDE SUMMER BOILER, POWER HOUSE, BUILDING NO. 28
ELMIRA CORRECTIONAL FACILITY
1879 DAVIS STREET
ELMIRA, NY**

September 9, 2016

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

HVAC SPECIFICATIONS

1. Page 230926-5, Paragraph 1.04 E.: Add the following Subparagraph:
 - “4. List of Completed Installations: Combustion Control and Instrumentation system shall have been provided by the Combustion Control and Instrumentation sub-contractor, approved by the Director’s Representative, and shall have been in operation for a period of not less than 5 years, in the State of New York.
 - a. The Director’s Representative will require the contractor to submit evidence of not less than 3 different installations where they have successfully provided Combustion Control and Instrumentation systems which integrated with a Preferred model number PCC-III for this period of time with the same control system submitted.
 - b. The 3 indicated installations shall be accessible for inspection by the Director’s Representative.
 - c. Contractor shall demonstrate seamless interoperability with the existing Preferred model number PCC-III system before the submittal is approved. Also prove the system is seamless including icons used, alarming approach, color usage, etc. The submission shall document compliance with all functionality required by the specification.”
2. Page 230926-9, ARTICLE 1.09 WARRANTY: Add the following Paragraph:
 - “B. Boiler No. 4 Controls – 3 Year Parts and Labor Warranty for the Following:
 1. BMS and CCS Controllers
 2. Field and Panel Devices, Instruments, Sensors”

HVAC WORK DRAWINGS

3. Drawing No. M-102, DRAWING NOTES, Note 3: Delete this Note in its entirety and replace with the following:
“3. Contractor shall remove (2) 1/2" instrument airlines and a 1 1/2" compressed airline on the east side of the boiler down to the floor penetration as noted on M-706.”
4. Drawing No. M-102, DRAWING NOTES, Note 4: Delete this Note in its entirety and replace with the following:
“4. Existing floor penetrations to be reused on east side of boiler. Refer to Drawing M-107 and M-712 for floor penetrations to be reused.”

ELECTRICAL WORK

5. No Addenda at this time.

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction