




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 6 TO PROJECT NO. 44990

**CONSTRUCTION WORK
REPLACE ROOFS, SIDING, WINDOWS, AND DOORS
TABERG RESIDENTIAL CENTER FOR GIRLS
10011 TABERG-FLORENCE ROAD
TABERG, NY**

July 09, 2015

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

BIDDING REQUIREMENTS

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last day for receipt of bids is changed from Wednesday, July 15, 2015 to Wednesday, July 29, 2015.

CONTRACT DRAWINGS

1. Drawing Nos. A-101, A-101B, A-102, A-103, A-103B, A-104, A-105, and A-106: Add the following Note:

“TO THE BEST OF OUR KNOWLEDGE, BELIEF, AND PROFESSIONAL JUDGMENT, SUCH PLANS AND SPECIFICATIONS ARE IN COMPLIANCE WITH THE 2014 NYS ENERGY CONSERVATION AND CONSTRUCTION CODE.”
2. Drawing No. A-105: At the Door and Window Schedule delete Type M Glazing.

SPECIFICATIONS

2. Page 072100-2, Subparagraph 2.01.A 1.b.: Delete this Subparagraph in its entirety and replace with the following:
“a. 1 Inch Thick: R=5.7@ 40 degrees F and 7.2 @ 75 degrees F.”
3. Page 072100-2, Paragraph 2.01 B.: Delete this Paragraph in its entirety.
4. Page 073113-5, Subparagraph 2.02 F.2.a.: Delete this Subparagraph in its entirety and replace with the following:
“a. Minimum R = 30.”

5. Page 082200-1, PART 1 GENERAL: Add the following Article:

“1.05 QUALITY ASSURANCE

A. Exterior Doors:

1. Maximum U value of 0.77.
2. Maximum Air Infiltration Rate of 0.20 CFM/FT², when tested in accordance with AAMA/WDMA/CSA101/I.S.2/A440 or NFRC 400.”

6. Page 085200-1, Article 1.04, QUALITY ASSURANCE: Add the following Paragraph:

“D. Performance Requirements:

1. Maximum U value of 0.43.
2. Maximum Air Infiltration Rate of 0.20 CFM/FT², when tested in accordance with AAMA/WDMA/CSA101/I.S.2/A440 or NFRC 400.”

7. SECTION 088100 – GLASS AND GLAZING: Delete this section entirely from the Project Manual

END OF ADDENDUM

Margaret F. Larkin
Executive Director