



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. 45066

**CONSTRUCTION WORK
REPLACE FLOOR DRAINS AND SEPTIC SYSTEM
1576 TUPPER ROAD
DOT REGION 2, HAMILTON COUNTY
LONG LAKE, NY 12847**

May 26, 2015

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATION GROUP

SECTION 011000 SUMMARY OF THE WORK: Discard the section bound in the Project Manual and substitute the attached Section (pages 011000 -1 thru 011000-5) noted "Revised 5/26/2015".

END OF ADDENDUM

Margaret F. Larkin
Executive Director

SECTION 011000

SUMMARY OF THE WORK (Revised 5/26/2015)

PART 1 GENERAL

1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. The title and location of the Work is printed on the cover of this Project Manual.
- B. Type of Contract: Fixed price.

1.02 SUBSTANTIAL AND PHYSICAL COMPLETION DATES

- A. Substantially complete the Work within 395 days after the Agreement is approved by the Comptroller.
 - 1. The time allocated for the performance of work under this contract includes 10 days for notification of the Contractor of the Comptroller's approval of the Agreement.
 - 2. The approval of the Agreement by the Comptroller constitutes the filing of the Contract Documents as a public record and notice to the Contractor that a fully executed contract exists between the Contractor and the State.
- B. Physically complete the Work within 90 days after the established Substantial Completion date.

1.03 CONTRACT AWARD SUBMITTALS

- A. Submittal No. 1 (by Contractor responsible for submittals website as specified in Specification Section 013300): Establish the subscription with the electronic submittals website provider as described in ELECTRONIC SUBMITTALS Article in Specifications Section 013300, and submit not later than 5 days after approval of the Contract by the Comptroller.
- B. Submittal No. 2: Submit the CONTRACTOR'S LIST OF SUBCONTRACTORS-SUPPLIERS information required in SCHEDULES AND RECORDS Article in Specification Section 013000 not later than 15 days after approval of the Contract by the Comptroller.
- C. Submittal No.3: Submit the CONTRACTOR'S PROGRESS SCHEDULE information required in SCHEDULES AND RECORDS Article in Specification Section 013000 not later than 15 days after approval of the Contract by the Comptroller.

1.04 PHASING

- A. PHASE 1: This portion of the Work consists of the replacement of the septic system, including but not limited to: excavation & trenching for new piping, septic tank, distribution box and leach field; provision of the new concrete septic tank, distribution box and piping; connection of piping to existing building drainage piping; backfilling & restoration of site areas (grading, seeding & paving where indicated). This phase to be performed between Award date and November 1st, 2015.
- B. PHASE 2: This portion of the Work consists of the provision of the floor drain system, including but not limited to: interior saw cutting of concrete floor slabs and trenching for new piping below slabs; provision of the new engineered drainage system & all associated piping/cleanouts/sumps/etc.; backfilling & provision of concrete slabs to match existing elevations & pitches; excavation at exterior for piping, two large concrete holding tanks, oil/water separator & catch basin; connection of interior piping to new catch basin and backfilling & restoration of site areas (grading, seeding & paving where indicated). This phase to be performed between May 1st and August 31st, 2016.

1.05 RESTRICTED WORK PERIOD

- A. Do not perform the Work of Phase 2 between November 1st and May 1st unless approved otherwise, in writing, by the Director. During this period, the Owner will require full use of the building interior for their snow & ice operations.
- B. Sow grass seed between April 1 and May 15th or between August 15th and October 15th, except as otherwise approved in writing by the Director.

1.06 ITEMS NOT INCLUDED

- A. The following items shown on the Drawings are not included in this Contract:
 - 1. Items indicated "NIC" (Not in Contract).
 - 2. Existing construction, except where such construction is to be removed, replaced, or altered.

1.07 CONFINED SPACE

- A. Comply with confined space and permit-required confined space as defined in Title 29, Part 1910, Section 146 of the Code of Federal Regulations (29CFR 1910.146).
- B. Comply with Safety Requirements for Confined Spaces (ANSI/ASSE Z117.1-2009).
- C. All spaces shall be treated as permit-required confined spaces until the Contractor and/or subcontractors are able to re-classify the space to a non-permit confined space as per 29CFR 1910.146 and ANSI/ASSE Z117.1-2009.

- D. Indicated confined spaces are not intended to limit or define Contractor's or subcontractors' regulatory compliance requirements.
- E. For the purpose of inspecting ongoing work, furnish at no additional cost to the State, personnel, as directed, to allow the Director's Representative to enter confined space and permit-required confined space in compliance with Title 29, Part 1910, Section 146 of the Code of Federal Regulations (29CFR 1910.146).

1.08 OCCUPANCY

- A. This is an occupied Facility. The building, except for the work areas, will be occupied during execution of the Work. Ingress to and egress from the building shall be maintained at all times.

1.09 CONTRACTOR USE OF PREMISES

- A. Work hours shall be as established by the Facility authorities through the Director's Representative. The work hours established are 7:00 a.m. to 3:30 p.m., Monday thru Friday.
- B. Inform the Director's Representative of work area access requirements. The Director's Representative will coordinate and schedule the requirements with Facility staff to obtain and ensure timely availability of work areas.
- C. Check in with the Facility Representative, as directed, at the beginning of each work day. Furnish information regarding where employees will be working during the day.
- D. Comply with the Facility's Visitor Identification Policy. A copy of the current policy will be distributed at the initial job meeting.
- E. The following items are not allowed on the Site or on Facility premises.
 - 1. Firearms, ammunition, weapons, and dangerous instruments (other than tools required for the Work).
 - 2. Alcoholic beverages and persons under the influence of same.
 - 3. Illegal controlled substances and persons under the influence of same.
 - 4. Cameras (except with written permission from the Director's Representative).
- F. Comply with Facility policies relating to smoking at the Site.
- G. Routes of ingress and egress within the building to the location of the Work shall be as directed by the Director's Representative.
- H. Store materials and perform the Work so that pedestrian and vehicular traffic is not obstructed.
- I. Do not diminish the level of life safety during performance of the Work.

- J. Furniture and portable equipment, which interferes with execution of the Work, will be removed and reset by Facility personnel.
- K. Be responsible and accountable for employees, suppliers, subcontractors and their employees, with regard to their use of the premises. Direct them to comply with the Facility Regulations and with the security and traffic regulations.
- L. Furnish Facility authorities with a telephone number or method to contact the supervisor for the Work in case of an emergency after work hours, including weekends and holidays.
- M. Comply with applicable federal and State of New York Right-to-Know Law provisions. Provide Material Safety Data Sheets (MSDS) documents for products that have MSDS data prior to use on the project site.
 - 1. Upload and maintain electronic MSDS documents on the Submittals Website (MSDS tab).
 - 2. MSDS tab is organized by prime contracts. To be readily identified, name products with MSDS by specification section number and product name.
 - 3. Supply and maintain one hard copy of the appropriate MSDS on the project site and one hard copy with the Facility's Right-to-Know Information Officer.
- N. Direct employees to be watchful for people in or near the work area where safety hazards may be present. Notify the Facility Safety/Security Department, if necessary, to remove them from the work area or Site.
- O. Report fire and other emergency situations to the Facility Safety/Security Department immediately.

1.10 REFERENCE SPECIFICATIONS AND STANDARDS

- A. Comply with the requirements of the various specifications and standards referred to in these Specifications, except where they conflict with the requirements of these Specifications. Such reference specifications and standards shall be the date of latest revision in effect at the time of receiving bids, unless the date is given.
- B. DOT Specifications: If the abbreviation DOT appears in these Specifications, it shall mean the most current edition of the New York State Department of Transportation, Office of Engineering specifications entitled "STANDARD SPECIFICATIONS - CONSTRUCTION AND MATERIALS", including all applicable Addenda in effect at the time of receipt of bids. The DOT specifications may be purchased from the Department of Transportation, Plan and Publication Sales, 50 Wolf Road, Albany, NY 12232, (518) 457-2124.

1.11 LAYING OUT

- A. Examine the Contract Documents thoroughly and promptly report any errors or discrepancies to the Director's Representative before commencing the Work.

B. Lay out the Work in accordance with the Contract Documents.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

END OF SECTION