



**DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 1 TO PROJECT NO. 45121

**CONSTRUCTION WORK, HVAC WORK & ELECTRIC WORK
REPLACE ROOF
TROOP B HEADQUARTERS
1097 ROUTE 86
RAYBROOK, NY 12977**

May 17, 2016

<p>NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

C-Contract

1. Sheet A-101
Drawing 1/A-101: CHANGE note to Evidence Room 40 to read as follows:
“CAREFULLY REMOVE EXISTING ACOUSTIC CEILING TILES AND GRID;
COORDINATE WITH H-CONTRACTOR AND MECHANICAL REMOVALS. REINSTALL
TILE AND GRID WHEN MECHANICAL REMOVALS ARE COMPLETED. PROVIDE
TEMPORARY DUST BARRIER THROUGHOUT ALL WORK.”
2. Sheet A-101
Drawing 1/A-101: CHANGE note to Evidence Room 40 to read as follows:
“1-HR RATED GYPSUM WALL BOARD CEILING REPAIR AT DUCT REMOVAL.
ASSUME 9 SQUARE FEET @ ½” GYPSUM WALL BOARD, TYPE X, 2 LAYERS. TAPE
ALL SEAMS.”
3. Sheet A-102
Drawing 1/A-102: At Roof Area 7 Chimney - DELETE note that chimney flues will be removed under a separate contract. The C-Contractor shall be responsible to remove the flue tiles above the chimney line.
4. Sheet A-503
Drawing 2/A503: CHANGE ALL REFERENCES TO BLOWN-IN INSULATION THICKNESS FROM 16” TO +/- 11.”.

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction