



**DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 1 TO PROJECT NO. 45126

**CONSTRUCTION WORK
DEMOLISH BUILDING NO. 2
STATE OFFICE BUILDING CAMPUS
1220 WASHINGTON AVENUE
ALBANY, NY**

February 11, 2016

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 015000-1, ARTICLE 1.08 TEMPORARY FENCE ENCLOSURE: Delete this Article in its entirety and replace with the following:

“1.08 TEMPORARY FENCE ENCLOSURE

- A. Install temporary fence not less than 8 feet in height above grade using a combination of existing materials currently installed on site and contractor provided fencing materials as noted in the Contract Drawings.
 1. Relocated Existing Fence: 8 feet in height above grade, fence fabric #9 galvanized steel, top and bottom rails between all posts, secured with bolted connections. Provide caps at tops of all posts, and do not reinstall barbed wiring and arms.
 2. Contractor Provided Fence: 8 feet in height above grade, fence fabric #9 galvanized steel, with tension wire at top, twisted selvage at top, knuckled selvage at bottom, wind screen, brace and tension bands, brace rails with truss rods, line posts, corner posts and end posts with caps, tension bars at corner / end posts and required gates – non barbed wire fence).
- B. Fabric: #9 gage galvanized steel, or equal gage aluminum, woven together into 2 inch diamond mesh, with both top and bottom edges having a twisted and barbed finish.
- C. Posts, Rails, and Connections: Standard galvanized steel products of an approved manufacturer, of the size and types as required and approved.

- D. Gates (Relocated Existing Fence and Contractor Provided Fence): Provide access gates for passage of employees and materials, complete with padlock. Fabricate gates with galvanized steel pipe perimeter covered with same fabric specified for fence. Furnish the Director's Representative with 2 keys per gate.
- E. Erection (Relocated Existing Fence and Contractor Provided Fence): Set posts 4 feet into the ground and not more than 10 feet apart. Install bottom rail not more than 2 inches above existing grade. Pull fabric taut and wire tightly to posts and rails at not more than 2 feet on center.
- F. Maintain the contractor provided fence enclosure and the relocated existing fence enclosures throughout the length of the Contract, or until directed to be removed. Replace all items or portions of fence enclosure damaged or destroyed.”

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction