




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 3 TO PROJECT NO. 45145

**CONSTRUCTION WORK
PROVIDE DRY FOOD STORAGE BUILDING,
WALK-IN COOLER AND FREEZER
RED HOOK RESIDENTAIL CENTER
531 TURKEY HILL ROAD
RED HOOK, NEW YORK 12571**

February 18, 2015

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

DRAWINGS

1. DRAWING E-101, RESIDENCE BUILDING BASEMENT - ELECTRIC:
 - a. Note – wiring from existing panel MDP:
Delete “4-#3 Cu & 1-#8 Cu GND in 1 ¼” C.”
Replace with “4 - #1/0 THHN/THWN & 1 #6 EGC in 1 ½” rigid metal conduit.
Continue the wiring in existing underground conduit from residence building basement to the existing generator building.”

2. DRAWING E-101, FOOD STORAGE BUILDING - ELECTRIC:
 - a. Note - underground conduit at Disconnect:
Delete “Existing spare 3” underground conduit to existing residence building basement.
See C-101 Site Plan.”
Replace with “Provide 4 - #1/0 THHN/THWN & 1 #6 EGC in existing spare underground conduit from residence building basement to existing generator building.
See C-101 Site Plan.”
 - b. Note - wiring within Generator Building:
Delete “4-#3 Cu & 1-#8 Cu GND.”
Replace with “4 - #1/0 THHN/THWN & 1 #6 EGC in 1 ½” rigid metal conduit from disconnect to existing 2” underground conduit and continue the conductors to panel FS through existing 2” underground conduit.”

END OF ADDENDUM

Margaret F. Larkin
Executive Director
Design and Construction