



# Office of General Services

DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242

---

## ADDENDUM NO. 2 TO PROJECT NO. 46049

### CONSTRUCTION, HVAC, AND ELECTRICAL WORK UPGRADE ELECTRICAL DISTRIBUTION FACILITY GENERATOR & SWITCHGEAR WENDE CORRECTIONAL FACILITY 3040 WENDE RD ALDEN, NY

June 1, 2026

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.  
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

#### BIDDING REQUIREMENTS – COMMON

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last date for receipt of bids is changed from Wednesday, June 3, 2026, to Wednesday, June 10, 2026.

#### ELECTRICAL WORK DRAWINGS

2. Drawing No. E-001:
  - a. Notes Applicable to All Electrical Drawings, Change Note 27 to Read:

“27. PROVIDE ALL LABOR AND MATERIAL FOR PROVIDING ELECTRICAL DUCTBANKS INCLUDING BUT NOT LIMITED TO EXCAVATION, SPOILS DISPOSAL, CONCRETE REMOVALS, PROOF ROLLING, COMPACTION, FORMS, REBAR, CRUSHED STONE, SAND, CONCRETE, BACKFILL, AND TOPSOIL. C CONTRACT PROVIDES TOPSOIL LEVELING, SEEDING, SIDEWALKS, CURBS, ASPHALT SAWCUTTING, ASPHALT MILLING, ASPHALT REMOVALS, AND ASPHALT RESTORATION.”

3. Drawing No. E-507:
  - a. Detail 1, Change Note 2 to Read:

“2. C CONTRACT TO EXTEND FULL DEPTH ASPHALT REMOVAL AND  
REPLACEMENT MINIMUM 12 INCHES BOTH SIDES OF CONCRETE  
DUCTBANK.”

- b. Detail 1, Change Note 3 to Read:

“3. C CONTRACT TO MILL EXISTING PAVEMENT 1-1/2” DEEP, 18” MINIMUM  
BEYOND SAW CUT LINES.”

**END OF ADDENDUM**

Brady Sherlock, P.E.  
Director, Division of Design  
Design & Construction