



**DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 2 TO PROJECT NO. 47208

**HVAC AND ELECTRICAL WORK
REPLACE HEATING SYSTEM OFFICE AND GARAGE
DOT REGION 8, DUTCHESS COUNTY
HOLLOW ROAD AND TACONIC PARKWAY
CLINTON CORNERS, NY**

May 12, 2023

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

CHANGES TO ADDENDUM NO. 1

1. Item No. 1: DELETE Subparagraphs 1.04 B.1 and 1.04 D.1.a.

HVAC WORK SPECIFICATIONS

2. Page 230700 – 6, Article 3.08, TYPE B - Heating Water (HS&HR): CHANGE to Read:
 - a. Pipe Size 1-1/4" & Less: 1-1/2" Minimum (Nominal) Insulation Thickness (Inches)
 - b. Pipe Size 1-1/2" & Over: 2" Minimum (Nominal) Insulation Thickness (Inches)

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction