



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 3 TO PROJECT NO. M2939

**ELECTRICAL WORK
REHABILITATE ELECTRICAL SUBSTATION, BLDG 76.
CREEDMOOR PSYCHIATRIC CENTER
80-45 WINCHESTER BOULEVARD
QUEENS VILLAGE, NY**

December 22, 2011

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

DRAWINGS

1. Drawing E-001: Add the following to Note 13.

The oil separator is to be cleaned and tested to verify satisfactory operation. Clean dirt and debris from bottom of sump and drain lines to verify free operation of float. Replace heater element. Oil separator sump is manufactured by Curlee manufacture and is model JBE 12128-Z. The tank is manufactured by AFL Industries and is model SOS-4 w/OSV-4 and freeze protection.

2. Drawing E-001 and Drawing E-002: Add the following note to the Heater Wiring Detail on both drawings.

Wiring in cubicles for heater elements should be installed in rigid galvanized steel conduit.

3. Drawing E-002: Add the following to Note 11.

New lightning arrestors are to be 27kV porcelain lightning arrestors.

4. Drawing E-002: Add the following to Note 8.

The new Remote Alarm Enclosure is to be installed in the Command Center located approximately 1,000 feet from the sub-station.

END OF ADDENDUM

James Dirolf, P.E.
Director of Design