



ADDENDUM NO. 1 TO PROJECT NO. M2988

**HVAC WORK
REPLACE STEAM AND CONDENSATE LINES
BUILDING. NOS. 149 & 150
MOHAWK CORRECTIONAL FACILITY
PO BOX 8450
ROME, NY**

December 10, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

- 1) Page 011000 – 2, Paragraph 1.04 B: Delete this Paragraph in its entirety.
- 2) Page 011000 – 2, Sub-Paragraph 1.06 E. 1.: Delete this Sub-Paragraph in its entirety.
- 3) Page 230721 – 2, Paragraph 1.04 C: Delete this Paragraph in its entirety.
- 4) Page 232101 – 6, Change Paragraph 1.07 A. to Read:

“A. Special Warranty: The one year period required by paragraph 9.8 of the General Conditions is extended to 2 years for the Work of this Section. Refer to Supplementary Conditions. “
- 5) Page 232101 – 6, Article 1.09: Delete this Article in its entirety.
- 6) Page 260523 – 1, Article 3.01, Add the Following Paragraphs:
 - “B. Provide 200 ft of 2#12, 1#12G, ½” conduit to sump pump control panel from source panel. Source panel location to be determined. Verify actual power requirements with sump pump control panel manufactures data prior to commencement of work. Assume 20A-1P circuit breaker exists in source panel.
 - C. Provide 200 ft of 2#12, 1#12G, ½” conduit to leak detection system panel from source panel. Source panel location to be determined. Verify actual power requirements with leak detection system control panel manufactures data prior to commencement of work. Assume 20A-1P circuit breaker exists in source panel.”

END OF ADDENDUM

James Dirolf, P.E.
Director of Design

Updated 02/07/2008
Printed 12/10/2012