




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



**ADDENDUM NO. 1 TO PROJECT NO. M3021
CONSTRUCTION WORK
REPLACE MAIN BUILDING ENTRANCE DOORS
STATE ARMORY
93-05 168TH STREET
JAMAICA, NY**

July 31, 2014

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 011000 – 3, Change Paragraph 1.08 H to Read:
“H. No space is available to store materials on site, remove materials at the end of the day.
Perform the Work so that pedestrian and vehicular traffic are not obstructed. “
2. Page 081123 – 2, Article 1.04, Add the following paragraph:
“D. Door Mock Up:
 1. Provide a replacement mock up door. Do not proceed with other replacement doors until the mock up door has been approved by the Director's Representative.”

DRAWINGS

1. Drawing G-001:
 - a. TENANT SAFETY PLAN, Add to Note 3. B. the following sentences:

“Entrance opening(s) need to be made secure for the duration door(s) are missing. One set of corresponding interior and exterior doors will remain open, operational and securable for pedestrian egress at all times.”
 - b. TENANT SAFETY PLAN, Replace Notes 4.A, 4.B, 4.C and 4.D as follows:

“4. A. One (1) approximately 45 cu. ft. lock box storage container will be allowed to remain overnight in the work, provided egress is not blocked. Flammable, Toxic, and Corrosive materials are prohibited. No other storage is available unless otherwise approved by the Director Representative”
2. Drawing A-200:
 - a. Transom note, Change Note to read:

“Remove existing single pane glazing and glazing stop from transom and install new insulated glazing in existing frame. Work shall include reinstallation of stop in new location and re-tapping stop fasteners to accommodate thicker glazing in existing framing. Perform transom glazing work per approved shop drawings. (TYP.)”

- b. Page Note, Replace Note 1 to read:

“1. Prepare, clean and restore as per specification section 057700, all exposed surfaces of metal window framing and door framing.”

- c. Drawing Note, Add Note:

“Relocate conduit and power on doors frame as required and restore to original location at the completion of work.”

3. Drawing A-201:

- a. Transom note, Change Note to read:

“Remove existing single pane glazing and glazing stop from transom and install new insulated glazing in existing frame. Work shall include reinstallation of stop in new location and re-tapping stop fasteners to accommodate thicker glazing in existing framing. Perform transom glazing work per approved shop drawings. (TYP.)”

- b. Page Note, Replace Note 1 to read:

“1. Prepare, clean and restore as per specification section 057700, all exposed surfaces of metal window framing and door framing.”

- c. Drawing Note, Add Note:

“Prepare, clean and restore existing solid 4' x 7' interior office bronze door, door frame (jamb and header), and bronze door hardware, location in the facility lobby. Remove all dirt, oxidation, calcium deposits, organic growth and atmospheric soiling using approved methods and materials. Repair all holes, cracks, missing or deteriorated surfaces, dents and scratches, etc. using approved methods and in-kind materials to provide a uniform and consistent surface and appearance. Re-patina using an approved chemical process to match the approved color sample. Provide a coating of an approved clear protective lacquer compatible with the bronze and the chemical patination.”

- d. Drawing Note, Add Note:

“Relocate and maintain operational existing Exit Sign, move to location over door that is being utilized to remain open for pedestrian egress. Relocate conduit and power as required and temporarily support Exit Sign. Restore Exit Sign, conduit and power back to original location at the completion of work.”

END OF ADDENDUM

Margaret F. Larkin
Acting Executive Director