




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 1 TO PROJECT NO. Q1462

**CONSTRUCTION WORK
REPAIR FOUNDATION, SUNNYCROFT, BUILDING NO. 44
WILLARD DRUG TREATMENT CENTER
7116 COUNTY ROUTE 132
WILLARD, NY**

April 18, 2012

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 040122 – 1, Article 1.03, Add the following paragraph:
 - “C. Quality Control Submittals:
 1. Submit shoring plans and calculations for record in accordance with the contract drawings.”

2. Page 040122 – 8, Change paragraph 3.10 B to read:
 - “B. Repointed and reconstructed surfaces utilizing pointing mortar shall be kept moist and protected from extreme heat, freezing, high winds, and direct sunlight for a least a 72 hour period after finishing. These areas shall also be protected from rain for at least 12 hours after finishing. The contractor shall provide a written work plan to the Director’s Representative for approval prior to beginning repointing or reconstruction. The work plan shall describe proposed methods of maintaining moist conditions of the pointing mortar at the end of the contractor’s work day and work week. Pointing mortar not kept moist for 72 hours will be removed and replaced at no cost to the State.”

3. Page 044300 – 4, Article 3.05, Add the following paragraph:
 - “C. Repointed surfaces shall be kept moist and protected from extreme heat, freezing, high winds, and direct sunlight for a least a 72 hour period after finishing. Repointed areas shall be protected from rain for at least 12 hours after finishing.”

4. Drawing No. G-002
 - a. GENERAL NOTES, Replace General Note 10 with:
"10. THE CONTRACTOR SHALL OBTAIN THE SERVICES OF A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER TO DESIGN THE SHORING SPECIFIED ON THE CONTRACT DRAWINGS. THE ENGINEER IS TO VERIFY SHORING REQUIREMENTS AND LOADS AT THE SITE BEFORE PREPARING STAMPED SHORING DRAWINGS. SHORING LOADS ON THE CONTRACT DRAWINGS ARE FOR USE BY THE CONSTRUCTION CONTRACTOR FOR BID PREPARATION ONLY. PRIOR TO SHORING WORK, CONTRACTOR SHALL SUBMIT STAMPED SHORING DRAWINGS AND STAMPED CALCULATIONS FOR RECORD. THE ACTUAL SHORING TYPE, CONSTRUCTION AND DETAILS SHALL BE INCLUDED IN THE CONTRACTOR'S SUBMISSION. CONTRACTOR SHALL NOT BEGIN SHORING WORK PRIOR TO RECEIVING WRITTEN CONFIRMATION OF A COMPLETE SUBMITTAL FROM THE DIRECTOR'S REPRESENTATIVE."

5. Drawing No. C-502:
 - a. Detail 12: Change 12" dimension to 13".
 - b. Detail 12: Change "4" B12 BLEND" to "No. 2 COARSE AGGREGATE MATERIAL".
 - c. Detail 12: Change "NO. 2 COARSE AGGREGATE MATERIAL" to "4" B12 BLEND".

6. Drawing No. A-102:
 - a. PARTIAL BASEMENT PLAN WING 2:
Change "REPLACE BRICK ARCH IN KIND, CONTRACTOR TO PROVIDE TEMPORARY SHORING OF ARCH AT THIRD POINTS, REPLACING ONE PORTION OF THE ARCH AT A TIME. DL = 1,837 PLF".
to "REPLACE BRICK ARCH IN KIND USING NEW BRICK, CONTRACTOR TO PROVIDE TEMPORARY SHORING OF ARCH AT THIRD POINTS, REPLACING ONE PORTION OF THE ARCH AT A TIME. DL = 1,837 PLF".

7. Drawing No. A-503:
 - a. PORCH 1 RAMP ELEVATION, Add the following note:
NOTE: REMOVE BOTTOM 2-1/2" SECTION OF C8x11.5 AT 10 ADDITIONAL LOCATIONS, AS DIRECTED BY THE DIRECTOR'S REPRESENTATIVE, AND REPLACE WITH EQUIVALENT SECTION OF C8x11.5 AS SHOWN ON DETAIL G. TOTAL CHANNEL LENGTH TO BE REPAIRED, AS SHOWN ON ELEVATION PLUS AS DIRECTED LOCATIONS, IS 56'-0".

END OF ADDENDUM

James Dirolf, P.E.
Director of Design