




STATE OF NEW YORK  
OFFICE OF GENERAL SERVICES  
DESIGN AND CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242



---

---

**ADDENDUM NO. 1 TO PROJECT NO. Q1475**

**HVAC WORK  
PROVIDE FOUNDRY VENTILATION  
BUILDING NO. 3  
ELMIRA CORRECTIONAL FACILITY  
1879 DAVIS STREET  
ELMIRA, N.Y.**

October 28, 2011

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**HVAC WORK DRAWINGS**

1. Drawing No. M101, DRAWING NOTES: Add the following Note 8:
  - "8. Provide condensate pump CP-1 with the following performance characteristics:
    - a. Location: Air Compressor Room
    - b. Service: HC-1
    - c. Pump Quantity: 2
    - d. Pump Flow: 9 GPM
    - e. Pump Pressure: 20 psi
    - f. Pump Motor: 1/3 hp, 115V, 1 Phase
    - g. Condensate Receiver Capacity: 15 gallons
    - h. Design Equipment: Armstrong AFH"

James Dirolf, P.E.  
Director of Design