



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 2 TO PROJECT NO. Q1510

**ELECTRICAL WORK, HVAC WORK, ELEVATOR WORK
ELEVATOR MODERNIZATION/REPAIR
DMNA HEADQUARTERS
300 OLD NISKAYUNA RD
LATHAM, NY**

January 11, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual.
Acknowledge receipt of this Addendum in the space provided on the Bid Form.

BIDDING REQUIREMENTS

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last day for receipt of bids is changed from Wednesday, January 16, 2013 to Wednesday, January 30, 2013.

ELECTRICAL DRAWINGS

1. Drawing E-101 "RISER DIAGRAM"-Change the conduit and conductor size between ATS-1 to PP-EL-1 from "4#2, 1-1/2" C to 4# 2/0 in 2" C.
2. Drawing E-101 "RISER DIAGRAM"-The conduit and conductor size from the transformer "T" to PP-EL-2 shall be "4#2, 1-1/2" C".

END OF ADDENDUM

James Dirolf, P.E.
Director of Design