



STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 3 TO PROJECT NO. Q1567

**CONSTRUCTION WORK
CAMP SMITH WASTEWATER TREATMENT UPGRADES
CAMP SMITH
100 CAMP SMITH DRIVE
CORTLANDT MANOR, NY**

July 1, 2013

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

SPECIFICATIONS

1. Page 221123-1, Paragraph 2.01 A: Change “AD941-920HI” to read “AD-941-A02H1”
2. Page 221123-1, Paragraph 2.01 B: Change “0.50 GPH” to read “0.33 GPH”
3. Page 409443-2, Article 1.02, Add the following Paragraph:

“E. The Contractor shall provide all equipment, software, calibration of equipment, wiring and connections for a complete operational system. OGS will provide programming of the software and panels.”

DRAWINGS

4. Drawing G-002:
 - a. General Notes Column, Add the following note:

“19. Refer to Specification Section 023313, Underground Utility Locator Service, for the requirements of Contractor provided utility location.”

5. Drawing C-500:

- a. PLAN VIEW: Delete “AND SPARE CONDUIT” from the detail label indicator, 3/C-500.
- b. Detail 4/C-500: FIBERGLASS REINFORCED PLASTIC STORAGE SHED NOTES Column, Add the following note:

“2. Provide the following labeling in 3 inch high lettering contrasting the building color on the door:

SODIUM SULFITE STORAGE
AUTHORIZED PERSONNEL ONLY

Also Include a NFPA diamond, approximately 6” wide, as follow:

Flammable=0
Reactivity=1
Health = 1
White – Blank”

END OF ADDENDUM

James Dirolf, P.E.
Director of Design