




STATE OF NEW YORK
OFFICE OF GENERAL SERVICES
DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242



ADDENDUM NO. 4 TO PROJECT NO. Q1604

**HVAC AND ELECTRICAL WORK
PROVIDE TEMPORARY BOILER CONNECTIONS
FOR TRAILER MOUNTED EMERGENCY HOT WATER BOILER
DOWNSTATE CORRECTIONAL FACILITY
121 RED SCHOOLHOUSE ROAD
FISHKILL, NY 12524**

April 15, 2014

<p>NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

HVAC SPECIFICATIONS

1. Section 230523 Article 3.03.10: Change "High Temperature Water (HTS & HTR) 300 psig and less: Weld end, GV-8 gates, AV-8 globe or angles and CV-21 checks." To read "Medium Temperature Hot Water (MTHWS & MTHWR 300 psig and less: Weld end, GV-8 gates, AV-8 globe or angles and CV-21 checks."

HVAC DRAWINGS

2. Drawings M-200, M-400, M-501:
 - a. Replace butterfly valves with gate valves on all MTHWS and MTHWR piping.
3. Drawing M-200:
 - a. Drawing Note 9, Add "Contractor shall provide initial fill."

ELECTRICAL DRAWINGS

4. Drawing E103:
 - a. Provide 120 vac power to fuel tank heat tracing control panel, 1 pole, 20 amp, GFI breaker from panel PP-LV-TB in 1/2" conduit to FS-1. Coordinate location of connection at FS-1 with mechanical work contractor.

END OF ADDENDUM

Margaret F. Larkin
Acting Executive Director